

1 SIGNAGE PLAN - COLO 2
3/32" = 1'-0"

GENERAL SIGNAGE NOTE

- A. REFERENCE THE FOLLOWING MICROSOFT SIGNAGE GUIDELINES IN CONJUNCTION WITH SPECIFICATION SECTION 10 14 00
- B. MICROSOFT SITE SIGNAGE GUIDELINES / NEW CONSTRUCTION COMPLETE SIGNAGE PACKAGE REVISED SEPTEMBER 2013
- C. MICROSOFT BUILDING SIGNAGE GUIDELINES / NEW CONSTRUCTION COMPLETE SIGNAGE PACKAGE REVISED JANUARY 2015
- D. FOR SITE SIGNAGE, REFER TO CIVIL DRAWING AT DOUBLE DOORS WITH TWO ACTIVE LEAFS LOCATE SIGN ON WALL AT RIGHT HAND SIDE DOOR. AT DOUBLE DOORS WITH ONE ACTIVE LEAF, LOCATE SIGN ON THE INACTIVE LEAF OF DOOR.
- E. PROVIDE SIGN "BC-6-2" AT EACH BATTERY CABINET PER 2009 IFC 608.2.2 (TYP.)
- F. PROVIDE SIGN TYPE BC-3.2 (ARC FLASH HAZARD SIGN) AT EQUIPMENT POSING AS AN ARC FLASH HAZARD AND AS DIRECTED BY OWNER
- G. PROVIDE SIGN TYPE BC-4.1 (FIRE EXTINGUISHER SIGN) AT LOCATIONS WHERE FIRE EXTINGUISHER IS HIDDEN FROM VIEW. REFER TO FIRE PROTECTION SPECIFICATION AND MICROSOFT GUIDELINES.
- H. PROVIDE SIGN TYPE BC-5.1 AT FIRE RATED WALLS PER SPECIFICATION SECTION 10 14 00. REFER TO RCP DRAWINGS FOR TYPE AND LOCATION OF FIRE-RATED ASSEMBLIES.
- I. PROVIDE SIGN TYPE BI-4.1 (EMERGENCY RESPONSE MAPS) AT EVERY EXIT FOR EACH BUILDING PER THE MICROSOFT BUILDING SIGNAGE GUIDELINES. MAP INSERTS SHALL BE PROVIDED BY THE OWNER.
- J. REFER TO SIGNAGE DETAILS ON SHEET A-S-01-4 FOR GRID AND ROOM IDENTIFICATION SIGNS (SIGN TYPES BI-8.2, BI-8.4). COORDINATE GRID NUMBERS WITH TELECOM DRAWINGS.
- K. AT ROOM ID SIGNAGE (BI-1.0 AND BI-2.0 SERIES) WITH RAISED TACTILE LETTERING. MOUNT SIGN 48" MIN. FROM FINISHED FLOOR BOTTOM OF LOWEST LINE OF TACTILE LETTERING, OR 60" MAX. FROM FINISHED FLOOR TO BOTTOM OF HIGHEST LINE OF TACTILE LETTERING. MOUNT SIGN ON WALL AT LATCH SIDE OF DOOR, 5" FROM DOOR FRAME.
- L. PROVIDE TO OWNER (4) SIGN TYPE BI-2.2 PER BUILDING, WITHOUT PRINTED INSERTS, FOR MISC. OWNER SIGNAGE.
- M. REFER TO PLUMBING DRAWINGS FOR "INDUSTRIAL WATER DRAIN NO DUMPING" AND "NON-POTABLE WATER DO NOT DRINK" SIGNAGE. THESE SIGNS SHALL BE MOUNTED 5'-0" A.F.F.
- N. PROVIDE SIGN TYPE BC-4.1 AT ALL FIRE EXTINGUISHER AND FIRE EXTINGUISHER CABINET LOCATIONS.
- O. GC SHALL BE RESPONSIBLE FOR ALL SIGNAGE QUANTITIES AND COUNTS. COORDINATE WITH MSFT SIGNAGE GUIDELINES.



5405 Buford Hwy., Ste. 270
Norcross, GA 30071
678.580.3281

Microsoft FTY02

Sign Number
0000
Sign Type
XXXX

SO#: 6155
SR: KC
PM: SP
SCALE: N/A

DATE: 11/07/24
DSR: SP
SUBMITTED: 12/17/24
REVISED: 01/23/25
ADDED: 01/30/25
REVISED PER DRB02: 03/21/25
04/02/25 SP

These drawings were produced by IMG for the sole purpose of conveying our intended manufacturing techniques in the construction of the attached product. These manufacturing techniques are the property of IMG. Permission to copy, disclose to others, or distribute this drawing can only be obtained through a written consent with IMG.

SIGNAGE SCHEDULE

SIGN #	DESCRIPTION
BC-1.0	TACTILE EXIT SIGN
BC-1.9A	ENTERING ROOM
BC-1.9B	COLO FD ACCESS
BC-1.9C	FD HAZ SIGN
BC-4.1	EMERGENCY RESPONSE DEVICE - FIRE EXTINGUISHER
BC-5.1	FIRE RATED WALL - 1HR
BI-4.1	EGRESS ASSEMBLY AREA
BI-4.2	COLO GRID
BI-1.0	DOOR NAME PLATE NON-OFFICE
BI-2.0	ADA UNISEX RESTROOM ID
HAC-1	TYP HAC
HAC-2	DOF HAC
HAC-3	COLO GRID
ID-5	EXTERIOR DOOR LABEL
ID-5.2	INTERIOR EGRESS SOLID DOOR
ID-5.3	ALARM DOOR
ID-6.1	INTERIOR ENTRY COLO

Plumbing Engineering Lead	BRAD HUTCHINS / OLSSON
Fire Protection Engineering Lead	BRAD HUTCHINS / OLSSON
Electrical Engineering Lead	PATRICK TURNER / OLSSON
MECHANICAL Engineering Lead	WARREN HUMPHREY / OLSSON
Electrical Engineering Lead	KC CHADOMERE / OLSSON
Telecommunications / Network Engineering Lead	ANDY OHELMAN / OLSSON
Security Systems Engineering Lead	LYNN THACKERY / TEECOM
Geotechnical Engineering Lead	TOM KETTLER / OLSSON

No.	Date	Revisions
0	05/24/2024	ISSUE FOR CONSTRUCTION
18	03/14/2025	DRB 02

SIGN LABELS COVERED WITH THIS ARE SHOWN AS FIELD LOCATE IN A BLOCK OF SIGNS OR LABELED ON ANOTHER PLAN PAGE

SIGN LABELS COVERED WITH THIS ARE LABELED BUT MOVED TO MAKE ROOM FOR OTHER LABELS


BC-5.1 1 HOUR FIRE BARRIER DECALS - QTY 61
Field locate at 15' intervals on fire rated walls

2027	2028	2029	2030	2031	2032	2033	2034	2035	2036
2037	2038	2039	2040	2041	2042	2043	2044	2045	2046
2047	2048	2049	2050	2051	2052	2053	2054	2055	2056
2057	2058	2059	2060	2061	2062	2063	2064	2065	2066
2067	2068	2069	2070	2071	2072	2073	2074	2075	2076
2077	2078	2079	2080	2081	2082	2083	2084	2085	2086
2087									

BC-5.2 2 HOUR FIRE BARRIER DECALS - QTY 27
Field locate at 15' intervals on fire rated walls

2088	2089	2090	2091	2092	2093	2094	2095	2096	2097
2098	2099	2100	2101	2102	2103	2104	2105	2106	2107
2108	2109	2110	2111	2112	2113	2114			

BC-5.2 - 2 HR RATED AT BATTERY ROOM WALLS



Bar Code
CONFIDENTIAL - DO NOT DISCLOSE. This document is exempt from public disclosure under the Public Disclosure Act and Uniform Trade Secrets Act.

Package
FIT-OUT
Sheet Title/Number

ARCHITECTURAL -
SIGNAGE PLAN -
COLO 2

FTY02-A-S-01- 2