

2 SIGNAGE PLAN - COLO YARD NORTH TYP.
1/8" = 1'-0"



1 SIGNAGE PLAN - COLO YARD SOUTH TYP.
1/8" = 1'-0"

GENERAL SIGNAGE NOTE

A. REFERENCE THE FOLLOWING MICROSOFT SIGNAGE GUIDELINES IN CONJUCTION WITH SPECIFICATION SECTION 10 14 00
B. MICROSOFT SITE SIGNAGE GUIDELINES / NEW CONSTRUCTION COMPLETE SIGNAGE PACKA REVISED SEPTEMBER 2013
C. MICROSOFT BUILDING SIGNAGE GUIDELINES NEW CONSTRUCTION COMPLETE SIGNAGE PACKAGE REVISED JANUARY 2015
D. FOR SITE SIGNAGE, REFER TO CIVIL DRAWIN
E. AT DOUBLE DOORS WITH TWO ACTIVE LEAFS LOCATE SIGN ON WALL AT RIGHT HAND SIDE DOOR. AT DOUBLE DOORS WITH ONE ACTIVE LEAF, LOCATE SIGN ON THE INACTIVE LEAF O DOOR.
F. PROVIDE SIGN "BC-6.2" AT EACH BATTERY CABINET PER 2009 IFC 608.7.2 (TYP.)
G. PROVIDE SIGN TYPE BC-3.2 (ARC FLASH HAZA SIGN) AT EQUIPMENT POSING AS AN ARC FLA HAZARD AND AS DIRECTED BY OWNER.
H. PROVIDE SIGN TYPE BC-4.1 (FIRE EXTINGUISH SIGN) AT LOCATIONS WHERE FIRE EXTINGUISHER IS HIDDEN FROM VIEW. REFER TO FIRE PROTECTION SPECIFICATION AND MICROSOFT GUIDELINES.
I. PROVIDE SIGN TYPE BC-5.1 AT FIRE RATED WALLS PER SPECIFICATION SECTION 10 14 00 REFER TO RCP DRAWINGS FOR TYPE AND LOCATION OF FIRE-RATED ASSEMBLIES.
J. PROVIDE SIGN TYPE BI-4.1 (EMERGENCY RESPONSE MAPS) AT EVERY EXIT FOR EACH BUILDING PER THE MICROSOFT BUILDING SIGNAGE GUIDELINES. MAP INSERTS SHALL E PROVIDED BY THE OWNER.
K. REFER TO SIGNAGE DETAILS ON SHEET A-S-0 FOR GRID AND ROOM IDENTIFICATION SIGNS (SIGN TYPES B1-8.2, BI-8.4). COORDINATE GRI ID NUMBERS WITH TELECOM DRAWINGS.
L. AT ROOM ID SIGNAGE (BID-1.0 AND BID-2.0 SERIES) WITH RAISED TACTILE LETTERING, MOUNT SIGN 48" MIN. FROM FINISHED FLOOR BOTTOM OF LOWEST LINE OF TACTILE LETTERING, OR 60" MAX. FROM FINISHED FLO TO BOTTOM OF HIGHEST LINE OF TACTILE LETTERING. MOUNT SIGN ON WALL AT LATCH SIDE OF DOOR, 5" FROM DOOR FRAME .
M. PROVIDE TO OWNER: (4) SIGN TYPE BI-2.2 PE BUILDING, WITHOUT PRINTED INSERTS, FOR MISC. OWNER SIGNAGE.
N. REFER TO PLUMBING DRAWINGS FOR "INDUSTRIAL WATER DRAIN NO DUMPING" AN "NON-POTABLE WATER DO NOT DRINK" SIGNAGE. THESE SIGNS SHALL BE MOUNTED 5'-0" A.F.F.
O. PROVIDE SIGN TYPE BC-4.1 AT ALL FIRE EXTINGUISHER AND FIRE EXTINGUISHER CABINET LOCATIONS
P. GC SHALL BE RESPONSIBLE FOR ALL SIGNAG QUANTITIES AND COUNTS. COORDINATE WIT MSFT SIGNAGE GUIDELINES

SIGNAGE SCHEDULE

SIGN #	DESCRIPTION
BC-1.0	TACTILE EXIT SIGN
BC-1.1	ROOF ACCESS
BC-1.8	SPRINKLER VALVE
BC-1.9A	ENTERING ROOM
BC-1.9B	COLO FD ACCESS
BC-1.14	AUTHORIZED PERSONNEL ONLY
BC-1.16	NO SMOKING
BC-1.19	DIESEL
BC-3.1	HAZARD - NFPA CHEMICAL
BC-3.2	HAZARD - ARC FLASH
BC-4.1	EMERGENCY RESPONSE DEVICE - FIRE EXTINGUISHER
BC-9.1A	SPRINKLER ZONES
BC-10	DIRECTIONAL EGRESS SIGN
BI-4.1	EGRESS ASSEMBLY AREA
BID-1.2	DOOR NAME PLATE NON-OFFICE
ID-5	EXTERIOR DOOR LABEL
ID-5.2	INTERIOR EGRESS SOLID DOOR
PAC-1.1	GENERATOR ID - AHJ
PAC-1.2	GENERATOR ID - ELECTRICAL

img
www.imgbuilds.com
5405 Buford Hwy., Ste. 270
Norcross, GA 30071
678.580.3281

Microsoft FTY02

0000 XXXX — Sign Number / Sign Type

SO#:	6155
SR:	KC
PM:	SP
SCALE:	N/A

	DATE:	DSR:
SUBMITTED:	11/07/24	SP
REVISED PER RFI 159:	12/17/24	SP
ADDED:	01/23/25	SP
	01/30/25	SP
REVISED PER DRB02:	03/21/25	SP
	04/02/25	SP

These drawings were produced by IMG for the sole purpose of conveying our intended manufacturing techniques in the construction of the attached product. These manufacturing techniques are the property of IMG. Permission to copy, disclose to others, or distribute this drawing can only be obtained through a written consent with IMG.

BRAD HUTCHINS / OLSSON
Plumbing Engineering Lead: BRAD HUTCHINS / OLSSON
Fire Protection Engineering Lead: PATRICK TURNER / OLSSON
BAS Engineering Lead: WARREN HUMPHREY / OLSSON
Electrical Engineering Lead: KC CHADOMERE / OLSSON
Telecommunications / Network Engineering Lead: ANDY OHLMAN / OLSSON
Security Systems Engineering Lead: LYNN THACKERY / TEECOM
Geotechnical Engineering Lead: TOM KETTLER / OLSSON

Revisions

No.	Date	Description
0	05/24/2024	ISSUE FOR CONSTRUCTION
18	03/14/2025	DRB 02

Sector Key Plan



Bar Code

CONFIDENTIAL - DO NOT DISCLOSE. This document is exempt from public disclosure under the Public Disclosure Act and Uniform Trade Secrets Act.

Package
CORE/SHELL

Sheet Title/Number

ARCHITECTURAL - SIGNAGE PLAN - TYPICAL

FTY02-A-S-01-7

A-S-01-7

0' 2' 4' 8'